

NATIONAL INSTITUTE OF TECHNOLOGY, RAIPUR (C.G.)

APPROXIMATE ESTIMATE

Colour Washing Work of Warden Quarter E, F & G Type (Outer Side), at NIT Campus Raipur.

S.No	DSR-2013 Item No.	Description & Item Specification	Unit	Rate (Rs.)	Approx. Qty.	Amount (Rs.)
1	13.2	15 mm cement plaster on th rough side of single or half brick wall of mix :				
	13.2.1	1:4 (1 cement : 4 fine sand)	Sqm	168.55	12327.00	2077715.85
2	13.47	Finishing walls with Premium acrylic Smooth exterior paint with Silicone additives of required shade :				
	13.47.1	New work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm).	Sqm	90.00	36215.00	3259350.00
3	13.80	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prapare the surface even and smooth complete :	Sqm	85.40	36215.00	3092761.00
4	14.46	Removing dry or oil bound distemper, water proofing cement oaint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete:	Sqm	9.00	23888.00	214992.00
5	15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	Sqm	18.15	12327.00	223735.05
Total Amount Rs.						8868553.90
Say						8868554.00